

数 量 計 算 書

工 種 / 種 別 / 細 別				L-1	R-1							合 計		備 考
													合計 単位	
道路土工	掘削工	土砂												
		掘削	484.99										485.0 m3	
	作業土工	埋戻し	13.53										13.5 m3	
	残土処理工	残土処理	469.96										470.0 m3	掘-埋/0.9
構造物撤去工	構造物取壊し工	t=15cm以下 舗装版切断		32.00	49.90								81.9 m	
		t=15cm以下 舗装版取壊し	490.80										490.8 m2	
		有筋Co 構造物取壊し	6.30										6.3 m3	
	運搬処理工	路運搬処理（濁水）	0.106										0.11 m3	切断*0.130/100
		路運搬処理（As）	24.54										24.5 m3	取壊*0.05
		路運搬処理（有筋Co）	6.30										6.3 m3	
地盤改良工	置換工	RC-40、t=59cm 置換	267.52										267.5 m3	※
舗装工	アスファルト舗装工	RC-40、t=19cm 下層路盤	430.60										430.6 m2	
		RM-40、t=18cm 上層路盤	430.60										430.6 m2	
		再粗As（20）、t=5cm 基層	430.60										430.6 m2	
		再密As（20）t=5cm 表層	430.60										430.6 m2	
排水構造物工	側溝工	街渠側溝		20.00	34.36								54.4 m	
		□400×400 横断暗渠	28.00										28.0 m	
	集水樹工	街渠管理樹		1.00	2.00								3.0 基	
		φ200 取付管		1.00	1.00								2.0 箇所	
区画線工	区画線工	単線式区画線（実線150φ）	78.70										78.7 m	
		単線式区画線（セブトラ450φ）	28.00										28.0 m	
仮設工	仮締切工	仮設進入防止柵	N=23基											
		基礎	0.2×46	=9.2 t /個			ポール	0.024×23	=0.55 t /本	合計	9.75 t		9.8 t	

※地盤改良 下層路盤面積×深さ0.59+側溝延長×幅0.45×深さ0.55（舗装総厚0.05+0.05+0.18+0.19+0.59-側溝高0.51）

土工計算書

掘削（土砂）					掘削（床堀）				
測点	距離 m	断面積 m ²	平均断面積 m ²	土量 m ³	測点	距離 m	断面積 m ²	平均断面積 m ²	土量 m ³
N0. 0 + 0.000	0.000	6.90			N0. 0 + 0.000	0.000	0.10		
N0. 1 + 0.000	20.000	17.80	12.350	247.00	N0. 1 + 0.000	20.000	0.20	0.150	3.00
N0. 1 + 13.055	13.055	17.80	17.800	232.38	N0. 1 + 13.055	13.055	0.20	0.200	2.61
合計	33.055			479.38	合計	33.055			5.61

土工計算書

埋戻し(発生土)					盛土				
測点	距離 m	断面積 ㎡	平均断面積 ㎡	土量 ㎥	測点	距離 m	断面積 ㎡	平均断面積 ㎡	土量 ㎥
No.0 + 0.000	0.000	0.20			No.0 + 0.000	0.000	0.00		
No.1 + 0.000	20.000	0.50	0.350	7.00	No.1 + 0.000	20.000	0.00	0.000	0.00
No.1 + 13.055	13.055	0.50	0.500	6.53	No.1 + 13.055	13.055	0.00	0.000	0.00
合計	33.055			13.53	合計	33.055			0.00